

# Beach Dune System Restoration at West Galveston Island

Public Coordination Meeting  
August 4, 2010



ONE COMPANY | *Many Solutions\**



# Beach Nourishment Location






# Beach Nourishment Location






# Project Features





# Sand Source





# Sand Source



HDR



# Sand Placement Method

Hopper Dredge  
Anchored Offshore

Sand Being Discharged  
onto Beach Through  
Pipeline

Siesta Key, FL



# Sand Placement Method





# Sand Placement Method



South Padre Island, TX




# What to Expect During Construction

- Construction will proceed from east to west
- Up to six months to complete
- As work progresses, beach will be fenced off in half-mile increments
- Construction will be 24 hours/day, 7 days/ week
- Equipment on beach will primarily be bulldozers and large dredging pipe
- Beach sand may include some shell and small clay balls
- Sand will initially be darker



# What to Expect After Construction


- Wave will smooth the beach from the “construction” template to the “design template”





# What to Expect After Construction


- Wave will smooth the beach from the “construction” template to the “design template”





# What to Expect After Construction


- Wave will smooth the beach from the “construction” template to the “design template”





# What to Expect After Construction

- Wave will smooth the beach from the “construction” template to the “design template”





# What to Expect After Construction

- As beach is smoothed by waves, a temporary “scarp” (step) will form along the water’s edge





# What to Expect After Construction





# Funding Sources

- FEMA – Public Assistance
- FEMA – Improved Project
- Galveston County 2008 CIAP
- 2008 CIAP
- 2008 GOMESA
- GLO – CEPRA



# Anticipated Schedule

- Construction Proposals: Aug/Sep 2010
- Begin Sand Placement: Oct/Nov 2010
- Begin Dune Planting: Jan/Feb 2011
- Complete Construction: Mar/Apr 2011



# Questions?

## Contacts:

Texas General Land Office

Ray Newby

512-475-3624

[ray.newby@glo.state.tx.us](mailto:ray.newby@glo.state.tx.us)

HDR Engineering

Dan Heilman

361-696-3344

[daniel.heilman@hdrinc.com](mailto:daniel.heilman@hdrinc.com)